FieldTurf A Tarkett Sports Company | THE ULTIMATE SURFACE EXPERIENCE

BEYNON A Tarkett Sports Company

Date: May 6, 2021

To:
AJ Panter
Executive Director
Facility Support Services
Vancouver Public Schools
360-313-1043 P
360-798-9952 C
360-313-4776 F
aj.panter@vansd.org

From:
James Traynor
Beynon Sports
206-979-9792
jtraynor@beynonsports.com

Subject: **Kiggins Bowl and Discovery Middle School Track**
800 E 40th St, Vancouver, WA 98663

FieldTurf USA Inc. in conjunction with Beynon Sports is pleased to present the following proposal. Price estimates are based off of the KCDA purchasing program. KCDA is a member of The Association of Educational Purchasing Agencies (AEPA) program. The AEPA is a purchasing co-op that provides member schools with pre-determined preferential pricing by approved vendors. Since the product has already been bid at the national level, individual schools do not have to duplicate the formal bid process. AEPA IFB #020.

Kiggins Bowl Surfacing	
Scope: **Remove the existing track surfacing and asphalt cleaning:** ▪ Remove Track Surfacing at Southeast D-Zone **(Area D)**: 641 SY ▪ Clean All asphalt after surface removal is completed in preparation for new surfacing **Surfacing Installation:** ▪ Track Surfacing SE D-Zone: o Size: 641 Square (5,769 SF) o Product: BSS 100 (black)	
Base Bid Cost:	**$ 34,837.00**
Additive Alternate 1 - Remove the existing surfacing and clean the asphalt on the visitor sideline **(adjacent to Area A bordering the field)** and resurface with Acrylotex surfacing (355 square yards) – ADD TO BASE BID:	$8,005.00
Additive Alternate 2 - Remove Track Surfacing and clean the asphalt in front of grandstand bleachers **(Area B)** and resurface with BSS 100 track surfacing (1,160 square yards) – ADD TO BASE BID:	$ 64,043.00

Additive Alternate 1 - Remove the existing surfacing and clean the asphalt on the visitor sideline **(adjacent to Area A bordering the field)** and resurface with Acrylotex surfacing (355 square yards) – ADD TO BASE BID:

Discovery Middle School Track Surfacing	
Scope: Beynon Sports proposes to supply and install BSS 100 track surface on 3,935 square yards of surface area. Includes labor, material, equipment, transportation, and track lines/event markings.	
Size: 3,935 square yards	
Product: BSS 100	
Color: Red or Black	
Warranty: 5 years	
Durations: ▪ Track Surfacing Crew: 10 Days ▪ Track Striping Crew: 3 Days	
Base Bid Cost:	**$152,324.00**

Inclusions and Exclusions:

- **Pricing above includes payment and performance bonds**
- **Includes prepping of multiple penetrations through the asphalt area between the stands and field (vaults, manholes, cleanouts, etc.) as described during the preconstruction meeting with Beynon representatives.**
- Beynon Sports is a licensed contractor in the State of Oregon
- Beynon Sports acknowledges all Prevailing Wages and Travel Time
- Beynon Sports is a member of the American Sports Builders Association and maintains Certified Builders on staff
- Cure time on new asphalt and concrete is 28 days prior to receiving new track surface
- While surfacing and striping are being done, water systems must be curtailed, shut off or controlled so that no water falls on the track or event area surfaces.
- Prices valid for 90 days

If you have questions regarding the FieldTurf and Beynon SmartBuy Cooperative Purchasing Program, please contact Eric Fisher at: eric.fisher@smartbuycooperative.com.